

## SHIPYARD AND MARINA POTENTIAL RISKS

### All areas

Potential risk	Pedestrian risks
Prevention measures	<ul> <li>Always proceed with the car at walking pace, respecting the signs. Pedestrians must use the appropriate lane delimited by the horizontal blue stripe.</li> <li>Respect the signs present on site.</li> </ul>
Potential risk	Falling from stairs
Prevention measures	<ul> <li>Be very careful when carrying objects. Do not carry items that require both hands or prevent you from seeing steps.</li> <li>Help yourself with the handrails.</li> <li>Do not leave or deposit objects on the steps or landings.</li> </ul>
Potential risk	Slip
Prevention measures	<ul> <li>Use shoes suitable for walking on site (no slippers, open shoes, etc.).</li> <li>Avoid transiting in wet areas.</li> <li>Respect the access prohibitions present on site.</li> </ul>
Potential risk	Fire
Prevention measures	In the event of an emergency, remain calm and act quickly, however avoiding any behavior that could cause panic or hinder exodus. In the event of an evacuation, immediately suspend what you are doing, avoiding creating risk situations and go quickly and according to the shortest route to the assembly point indicated in the plans posted on site. At the assembly point, the emergency coordinator will carry out the roll call of the personnel.
Potential risk	Impact with objects
Prevention measures	<ul> <li>Obligation to wear a safety helmet.</li> <li>Obligation to wear safety shoes.</li> <li>Observe and respect the signs present on site.</li> </ul>
Potential risk	Suspended loads
Prevention measures	<ul> <li>Do not stand under suspended loads.</li> <li>Do not pass under suspended loads and always wear a helmet.</li> </ul>
Potential risk	Working vehicles moving
Prevention measures	The presence of people in the working area of mechanical means can cause serious injuries, even death. Those who necessarily find themselves near the machines must wear clearly visible clothing (preferably orange or red) or highly visible in the event of evening or night work. If it is necessary to approach the car, you must first make yourself visible to the driver by calling his attention from a safe position (never shouting from behind the silhouette of the vehicle). Subsequently, after having been sighted by the operator, wait for the machine to stop and, with the prior consent of the driver, only at this point approach the cab to communicate with the operator himself.
Potential risk	Other risks
	In the event of control and/or verification of maintenance, hauling, launching and storage activities carried out on the vessel, scrupulously follow the instructions received from Sudcantieri personnel, including any use of PPE that may become necessary.



## Yards

Potential risk	Impact with objects
Prevention measures	<ul> <li>Obligation to wear a safety helmet.</li> <li>Obligation to wear safety shoes.</li> <li>Observe and respect the signs present on site.</li> </ul>
Potential risk	Suspended loads
Prevention measures	<ul> <li>Do not stand under suspended loads.</li> <li>Do not pass under suspended loads and always wear a helmet.</li> </ul>
Potential risk	Working vehicles moving
Prevention measures	The presence of people in the working area of mechanical means can cause serious injuries, even death. Those who necessarily find themselves near the machines must wear clearly visible clothing (preferably orange or red) or highly visible in the event of evening or night work. If it is necessary to approach the car, you must first make yourself visible to the driver by calling his attention from a safe position (never shouting from behind the silhouette of the vehicle). Subsequently, after having been sighted by the operator, wait for the machine to stop and, with the prior consent of the driver, only at this point approach the cab to communicate with the operator himself.
Potential risk	Other risks
	In the event of control and/or verification of maintenance, hauling, launching and storage activities carried out on the vessel, scrupulously follow the instructions received from Sudcantieri personnel, including any use of PPE that may become necessary.

# Area 1 Via Fasano gate entrance

Potential risk	Car impact with gate
Prevention measures	Wait for the gate to open completely

# <u>Area 2</u> **Driveway entrance, parking area**

Potential risk	Car impact
Prevention measures	Follow the road signs. Signal with an acoustic signal only if strictly necessary. Keep a safe distance from other cars